



REGIONAL DISTRICT of Fraser-Fort George

March 30, 2026

Addendum No. 2

Invitation to Quote ES-26-08 Front Walkway Replacement – 155 George Street Regional District Office Building

The addendum is being issued prior to the closing of the Invitation to Quote to provide further information, make changes to, or to clarify the Contract Documents and is to be read, interpreted and coordinated with all other parts of the Contract Documents. In the case of a conflict with the balance of the documents, this Addendum shall govern. **Bidders shall attach a signed copy of this addendum to their submission.** This addendum shall form part of the Contract Documents.

This addendum is being provided in clarification to ITQ ES-26-08 released March 18, 2026.

Appendix A, Scope of Work and Specifications, Section 5.4 currently reads:

5.4 Reinforcement

- Reinforcement with #8 rebar at 300 mm O.C. each way. Minimum cover 50 mm

Shall be changed to read:

5.4 Reinforcement

- Reinforcement with 6mm wire mesh rebar at 200 mm spacing each way. Minimum cover 50 mm

Question 1: Regarding the trees in the highlighted areas on Pg 14 of the Invitation to Quote Package. Is the intention to box out around the bases of each tree? Or are we removing them entirely?

Answer 1: The trees are no longer there; the intention is to have a continuous concrete walkway. The planters that are currently in place will need to be replaced with the new concrete walkway.

Question 2: Are we reinstating the outlined boot scrubber.

Answer 2: Yes, please see Section 4. SCOPE OF WORK, subsection 4.2:

4.2 Demolition & Site Preparation

- Removal and disposal of existing surfaces, reinforcing, and receptacle poles c/w associated electrical cabling pulled back to nearest junction box

155 George Street, Prince George, BC V2L 1P8

ELECTORAL AREAS A, C, D, E, F, G AND H | MACKENZIE | MCBRIDE | PRINCE GEORGE | VALEMOUNT

- Retain existing fence structure and lampposts on north side of walkway
- Protect existing vegetation and landscaping
- Ensure site safety setup and erosion control (as required)
- Existing pedestrian grating to be reinstalled
- Existing curb and gutter to remain
- Existing City of Prince George sidewalk along George St. to remain

I/We hereby verify that we have considered this Addendum No. 2 in our ITQ submission.

Signature of Bidder

Name of Bidder

Date

Inquiries relating to this ITQ may be directed to:

Bryan Boyes, Utilities Leader
Phone: 250-960-4400
Email: environment@rdffg.bc.ca