



## REGIONAL DISTRICT of Fraser-Fort George

April 24, 2026

### Addendum No. 2

#### Invitation to Tender ES-26-10 Earthworks Services - Cell One Expansion- Foothills Boulevard Regional Landfill

The addendum is being issued prior to the closing of the Invitation to Tender to provide further information, make changes to, or to clarify the Contract Documents and is to be read, interpreted and coordinated with all other parts of the Contract Documents. In the case of a conflict with the balance of the documents, this Addendum shall govern. **Tenderers shall attach a signed copy of this addendum to their submission.** This addendum shall form part of the Contract Documents.

---

This addendum is being provided in clarification to ITT ES-26-10 released April 7, 2026.

**Question 1: Are there geotechnical reports or testing reports for the material located in the designated borrow pits. Can these be provided?**

Answer: Sieve testing was carried out for one project from a very specific area of the south pit. The scope of this project exceeds the area tested by an extremely wide margin and would not be considered representative. There are no specific geotechnical reports associated with this material available. As part of quality control requirements, contractors shall include necessary material testing. Tetra Tech will also perform supplemental quality assurance material testing.

**Question 2: Can you confirm that there is sufficient material volume in the borrow areas to complete the placement volume specified in the schedule of prices?**

Answer: Yes, there is sufficient material.

**Question 3: During the mandatory site meeting it was mentioned that the contractor will be required to excavate methodically and as directed in the borrow area. Does a pit development plan exist, and can this be shared?**

Answer: The excavation of material will be in compliance with the Ministry of Mines, (open pit), and as directed by the Engineer and Regional District. Specific development will depend on the location of materials to be excavated.

**Question 4: During the mandatory site meeting the South pit was only visible from afar. Will the contractor need to perform pit development such as clearing, grubbing, tripping in order to access required borrow volumes?**

Answer: The south pit has been previously developed, some though minimal, grubbing and clearing to be expected.

155 George Street, Prince George, BC V2L 1P8

[ELECTORAL AREAS A, C, D, E, F, G AND H](#) | [MACKENZIE](#) | [MCBRIDE](#) | [PRINCE GEORGE](#) | [VALEMOUNT](#)

---

rdffg.ca | 250-960-4400 | 1-800-667-1959

**Question 5: Temporary Facilities – is there specific area that will be made available for the contractor to set up wash facility and a site trailer? Will there be access to existing utility infrastructure, or are generators acceptable for providing site power?**

Answer: A space will be made available for the contractor to set up a site trailer and wash facility within the project area. No power is available so generators where required will be acceptable.

**Question 6: Can E-bonds be accepted?**

Answer: No

**Question 7: Quality testing frequencies are not specified in the contract documents. What level of quality testing can be expected to be required?**

Answer: Quality Control testing frequency shall be in the range of 7-8 tests per hectare per compacted lift, which equates to an approximate target of one test for every 200 m<sup>3</sup> of engineered fill.

**Question 8: Is there existing survey control for the site that the contractor can use to establish required benchmarks?**

Answer: Yes.

**Question 9: I want to confirm if the OHSP should be submitted with our bid submission, or if this is to be included only after contract award?**

Answer: The OHSP must be submitted by the successful bidder, please see the correction below.

**Part C, Section 8. WorkSafeBC, third paragraph currently reads:**

The Contractor will maintain an Occupational Health and Safety Plan (OHSP) and ensure that their employees and Subcontractors are well trained and aware of OHSP. The OHSP must be submitted with the tender documents and will be approved by the Engineer of Record and the Regional District prior to being discussed during the combined safety and construction kick off meeting. The Contractor shall identify a safety officer for the project duration and include this person by name in the OHSP.

Shal be changed to read:

The Contractor will maintain an Occupational Health and Safety Plan (OHSP) and ensure that their employees and Subcontractors are well trained and aware of OHSP. **The OHSP must be submitted by the successful bidder** and will be approved by the Engineer of Record and the Regional District prior to being discussed during the combined safety and construction kick off meeting. The Contractor shall identify a safety officer for the project duration and include this person by name in the OHSP.

I/We hereby verify that we have considered this Addendum No. 2 in our ITT submission.

\_\_\_\_\_  
Signature of Tenderer

\_\_\_\_\_  
Name of Tenderer

\_\_\_\_\_  
Date

Inquiries relating to this ITT may be directed to:

Laura Zapotichny, General Manager of Environmental Services  
Phone: 250-960-4400  
Email: [environment@rdffg.bc.ca](mailto:environment@rdffg.bc.ca)