



October 23, 2024

ADDENDUM No. 1

Invitation to Tender PS-24-07 COMMUNICATION TOWER INSPECTIONS

*The addendum is being issued prior to the closing of the Invitation to Tender (ITT) to provide further information, make changes to, or to clarify the ITT Documents and is to be read, interpreted and coordinated with all other parts of the ITT Documents. In the case of a conflict with the balance of the documents, this Addendum shall govern. **Bidders shall attach a signed copy of this addendum to their bid submission, failure to do so may result in a non-compliant bid.** This addendum shall form part of the Contract Documents.*

This addendum is being provided in clarification to ITT PS-24-07 released October 10, 2024.

Clarification 1: Cover Page: Change "MANDATORY SITE MEETING" to "OPTIONAL SITE MEETING".

Clarification 2: Invitation to Tenders 4.4: Replace "A mandatory site meeting will be held at 2259 Quinn Street South, Prince George BC at 01:00 pm PST on October 18, 2024." with "An optional site meeting will be held at 2259 Quinn Street South, Prince George BC at 01:00 pm PST on October 18, 2024.".

Clarification 3: The BC 1 Call for the sign installation shows a City fibre optic line running along the edge of the access (see attached letter from City of Prince George and the History Sheet). The electrical conduit to the sign must maintain a minimum clearance of 300 mm from the existing fibre optic line.

Clarification 4: When installing the electrical conduits near the west end of the construction area (see below screenshot on the left), it is likely that the existing concrete curb and edge (see screenshot below on the right) will be damaged or removed. The contractor shall restore any damaged or removed concrete to its original condition. Payment for this work is to be included in the lump sum payment for Pay Item 1.01: "Sign electrical conduit, wiring, and connection.".

Clarification 5: No additional parking spaces will be available outside the construction area during the construction period.

Clarification 6: The contractor will be responsible for providing site security throughout the construction period.

Clarification 7: Concrete lock blocks near the gate will need to be relocated and put back once paving is complete.

I/We hereby verify that we have considered this addendum in our proposal submission.

Proponent's Signature

Date

All inquiries relating to ITT PS-24-07 must be emailed to:
Bonnie Seitz, Community Services Leader, bseitz@rdffg.bc.ca